

To, BPCL ESTIMATE MUMBAI . India - 400038. Ph:,Fax:. <b>Vendor Code:300648</b>	<b>REQUEST FOR QUOTATION</b>			
<b>RFQ No/Date:</b> 6000808384 / 03.02.2015	<b>Collective RFQ Number/ Purchase Group</b> 1000226746 / E75-CONS GRP HAZIRA <b>Contact person/Telephone</b> AMOL BHOSALE/- <b>Fax :</b> - <b>Email:</b> amolb@bharatpetroleum.in <b>Our ref.:</b>			
<b>Material/Services required at:</b> Hazira Co-Op Depot Bharat Petroleum Corporation Ltd. Surat Hazira Road, P.O.Ichhapore Surat - 394510 India				
<b>Subject: CONSTRUCTION OF NRO AT DEVALIYA DIST NARMADA</b> Kind Attn: Please quote your lowest prices for the supply of materials/services as per details given below. The quotation shall show separately and clearly (without any corrections) the basic price, discount (%), packing & forwarding (%), excise duty (with relevant excise tariff no./chapter id), sales tax (VAT/CST), freight(%),Service tax,other charges, etc against each item separately, as applicable. <b>Foreign vendors shall always quote their FOB prices against each item.</b> Rates/charges quoted in the quotation shall be final and no additional charges/corrections will be accepted after the receipt of quotation unless the same is necessitated by BPCL in writing.  The quotation shall be put in a sealed envelope superscribed as " <b>QUOTATION FOR BPCL COL.No.1000226746</b> " and sent to us before due date & time.				
<b>Item</b>	<b>Material Description</b>	<b>Qty</b>	<b>Unit Delivery date</b>	<b>Unit Basic Rate (in Figures)</b>
00010	CONSTRUCTION OF NRO DEVALIYA-NFIM ITEMS		03.06.2015	
<b>The item 00010 covers the following services:</b>				
10	7006141 BLDG RCC SLAB WITH 1% RFT 1:2:4	0.500	M3 (Cubic meter)	
Providing and laying RCC with upto 1% reinforcement for slab using 20mm down metal incl. centering, shuttering and curing for 21 days.(RCC qty upto 2.0 cum only) 1:2:4 mix.				
Service Item 10: Unit basic rate in words _____				
20	7006144 BLDG RCC HYSD STEEL BARS	10,850.000	KG (Kilogram)	
Providing cold twisted HYSD steel bars of approved make of reputed concern for RCC				
<b>Page 1 of 44</b>	Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.	

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	work including straightening, cutting, bending, binding and placing in position of 8mm and above dia and M.S. round bars dia.			
	Service Item 20: Unit basic rate in words _____			
30	7006150 BLDG MASONRY BRICK FOUNDN CM 1:6	3.000	M3 (Cubic meter)	
	Brick masonry work in foundation using best quality, locally available bricks with a compressive strength of min 35 kq/Sq.cm. In CM 1:6			
	Service Item 30: Unit basic rate in words _____			
40	7006154 BLDG MASONRY BM IN SUP STR CM 1:6	87.500	M3 (Cubic meter)	
	Brick masonry work in superstructure using best quality, locally available bricks with a compressive strength of min. 35 kg/sqcm. In CM 1:6			
	Service Item 40: Unit basic rate in words _____			
50	7006160 BLDG MASONRY . HALF BK WITH STFR >1	33	M2 (Square meter)	
	Half brick masonry work for partition wall in CM 1:4 including RCC stiffeners (3nos 8mm dia on full length )at every 1.2 M height using locally available flyash bricks.			
	Service Item 50: Unit basic rate in words _____			
60	7006167 BLDG PLASTER IN CM 1:4 12MM THICK	769	M2 (Square meter)	
	Providing and laying cement plaster in CM 1:4, 12 mm thick including scaffolding, and curing complete			
	_____			

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	Service Item 60: Unit basic rate in words _____			
70	7006173 BLDG PLASTER . 15+6MM SPL	163	M2 (Square meter)	
	Providing and Laying sand faced cement plaster externally in two coats. 1st coat with CM 1:4 min.15mm thick and 2ndcoat with CM 1:3 min. 6mm thick including smooth or matt finishing the surface, including scaffolding, and curing complete including addition of approved waterproofing			
	Service Item 70: Unit basic rate in words _____			
80	7006176 BLDG PLASTER . NEERU FINISH	232	M2 (Square meter)	
	Extra for providing neeru finish on plaster for internal wall surfaces.			
	Service Item 80: Unit basic rate in words _____			
90	7006177 BLDG PLASTER . CHICKEN MESH	190	M2 (Square meter)	
	Supplying and fixing chicken mesh before plastering at junctions of walls and RCC members.			
	Service Item 90: Unit basic rate in words _____			
100	7006183 BLDG PLASTER . CONSTPUMP ISLAND MPD	4	RM (RUNNING METER)	
	Construction of pump island for MPDs as per std. Drawing.			
	Service Item 100: Unit basic rate in words _____			
Page 3 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
110	7006294 DOOR WIN FLOAT GLASS . 12MM TK	13.250	M2 (Square meter)	
<p>DOORS AND WINDOWS AND SHUTTERS Supplying; fitting fixing in position plain/frosted float glass of Modi float or equivalent for glazed show window duly fixing with metal/aluminium clamps/putty etc. complete as directed including transparent sealant as required. 12 mm thick glass panel</p> <p>Service Item 110: Unit basic rate in words _____</p>				
120	7006296 DOOR WIN AL FRAM 101x45 60M POW COAT	17.500	M2 (Square meter)	
<p>DO With 50 to 60 micron powder coated aluminium ORS AND WINDOWS AND SHUTTERS Providing and fixing frame work for fixed glass show window out of aluminium section size 101 x 45mm x 2.10 mm with PVC beading &amp; glazing clip of 0.071 kg/M. ( Jindal section or equivalent by weight)</p> <p>Service Item 120: Unit basic rate in words _____</p>				
130	7006302 DOOR WIN AL FRAM SLIDING 60M POW COAT	7.100	M2 (Square meter)	
<p>DOORS AND WINDOWS AND SHUTTERS Providing and fixing sliding window with pipe frame &amp; two track section or as directed with 5.0mm thick clear float glass. (a) Twotrack bottom Sec No 8687 (61.85 x 31.75 x 1.2mm thick) (b) Two track top Sec No 8758 (61.85 x 31.75 x 1.3mm thick) (c) Shutter : 8665 on side ( Top/Bottom Sec No 8663 (40 x 18 x 1.25mm thk) (d) Inter lock Sec No 8664 (40 x 18 x 1.1mm Thick) .Jindal sections or equivalent by weight) With 50 to 60 micron powder coated aluminium</p> <p>Service Item 130: Unit basic rate in words _____</p>				
140	7006308 DOOR WIN GL AND FR FUL GL POW COAT 12TK	4.250	M2 (Square meter)	
<p>Providing and fixing 50 to 60 micron powder coated aluminium door on floor spring without vertical members but with special section of size approx 90mm X 40 mm ( 3.48 kg/M) for top &amp; bottom fully glazed with float glass unit and comprising of with locking arrangement and 340mm thick glass handle round</p>				
Page 4 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	shape or SS handle duly polished of incl fitting etc complete. (Jindal sections or equivalent by weight). 12mm thick plain glass panes.			
	Service Item 140: Unit basic rate in words _____			
150	7006318 DOOR WIN PANEL & FR PART GL 60M POWCOAT	12	M2 (Square meter)	
	DOORS AND WINDOWS AND SHUTTERS Fabricating erecting in position door frame using sections partly aluminium panelled and partly glazed shutter of aluminium of the following sections. (a) Door outer frame Sec No 4605. (b) shutter bottom Sec No 4530 (c) Shutter top Sec No 4531 (d) shutter vertical Sec No 4504 (e) lock rail Sec No 4621 (f) 5 mm thick clear float glass (g) 10 gauge aluminium panel; with anodized aluminium hinges; handles on both sides; concealed vertical locks; openable from both the sides and tower bolts. (if required) ( Jindal sections or equivalent by weight) With 50 to 60 micron powder coated aluminium section			
	Service Item 150: Unit basic rate in words _____			
160	7006341 DOOR WIN . . FLOOR SPRING	2	EA (each)	
	DOORS AND WINDOWS AND SHUTTERS Providing and fixing Floor spring of Everite or equivalent make			
	Service Item 160: Unit basic rate in words _____			
170	7006344 DOOR WIN . . HYD DOOR CLOSER	2	EA (each)	
	DOORS AND WINDOWS AND SHUTTERS Providing and fixing hydraulic door closer Everite or equivalent			
	Service Item 170: Unit basic rate in words _____			
180	7006350 DOOR WIN . SINTEX DR AL FRAME	2.500	M2 (Square meter)	
Page 5 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	DOORS AND WINDOWS AND SHUTTERS Providing and fixing Toilet block door with powder coated aluminium frame and PVC (syntex) shutter with necessary fitting and fixture of approved make.			
	Service Item 180: Unit basic rate in words _____			
190	7006467 ELECTRICAL . HPF FL. FIXTUR 1x 40W	16	EA (each)	
	Supply, installation, testing and commissioning of prewired wall/ceiling/false ceiling mounted type HPF fluorescent light fixtures including providing and fixing tubes, chokes (5 to 5.5 WATT LOSS Maximum), starters, capacitors, earthing, connections and mounting arrangements etc. complete as required. 1x40W similar to Philips light fixture No.TMC 18/136			
	Service Item 190: Unit basic rate in words _____			
200	7006468 ELECTRICAL . HPF FL. FIXTUR 1x 20W	4	EA (each)	
	Supply, installation, testing and commissioning of prewired wall/ceiling/false ceiling mounted type HPF fluorescent light fixtures including providing and fixing tubes, chokes (5 to 5.5 WATT LOSS Maximum), starters, capacitors, earthing, connections and mounting arrangements etc. complete as required. 1x20W similar to Philips light fixture No.TBT 11/120			
	Service Item 200: Unit basic rate in words _____			
210	7006441 ELECTRICAL . S & F LIGHT POLE 7M 1/2Y	6	EA (each)	
	Supplying fabricating erecting light pole in CC 1:3:6, painting the pole with two coats each of red oxide primer and approved make/shade/quality enamel paint complete excluding cost of foundation. (Height will be considered from finished driveway level) 7mtr high single arm as per std drg.			
	Service Item 210: Unit basic rate in words _____			
220	7006446	6	EA	
Page 6 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	ELECTRICAL . LIGHTPOLE FOUN >5 TO 7M HT		(each)	
	Erecting supplied light pole in CC 1:3:6 including excavating in all types of soil as per our standard drg.no. E&P/RO/EL/02. and specification. upto 7mtr height			
	Service Item 220: Unit basic rate in words _____			
230	7006449 ELECTRICAL . LIGHTPOLE WIRE >5 TO 7M HT	6	EA (each)	
	Providing wiring of light/emblem pole internally with 3/20 PVC insulated copper wire of approved make and making necessary connections. upto 7 mtr height			
	Service Item 230: Unit basic rate in words _____			
240	7006456 ELECTRICAL . S & F WP JUNCTION BO 4 way	3	EA (each)	
	Installation of cylindrical underground tank without HD arrangement as per our std. drg. no. in masonry pit, after excavation in all kinds of soil, bailing out of water, lowering the tank, levelling and testing the tank hydrostatically with fresh water to a pressure of 0.36kg/cm <sup>2</sup> for 2 hrs. painting with 2 coats of PF4 applying Shalimar tar plastic 3 mm thick including cost of paint to exterior surface of the tank, back filling of earth 150 mm, layers including adequate watering, ramming etc. as per std. drawing incl. cleaning of the site, providing 3 mm thick compressed graphite asbestos at manhole cover incl. supply of materials, labour, complete to the satisfaction of Engineer-in-Charge with RCC/masonry kerb wall. 45 KL tank as per std drg no E&P/RET/T1/03A			
	Service Item 240: Unit basic rate in words _____			
250	7006457 ELECTRICAL . P&F FLP JT. BOX 2 way	6	EA (each)	
<b>Page 7 of 44</b>		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	Providing and fixing FLP Junction Box confirming to IS 2148 2 way			
	Service Item 250: Unit basic rate in words _____			
260	7006481 ELECTRICAL CABLE AL CABLE 3.5x25MM	50	RM (RUNNING METER)	
	CABLE LAYING Supply, laying, testing and commissioning of Al. Conductor cable PVC insulated PVC sheathed. 1100 V grade armoured cable in existing PVC conduit on walls / false ceiling / roof. Laid in cable tray with end termination's connections, earthing etc. complete as required 3.5 x 25 sq. mm			
	Service Item 260: Unit basic rate in words _____			
270	7006488 ELECTRICAL CABLE CU. CAB 3x1.5sq. mm	75	M (Meter)	
	CABLE LAYING Supply, laying, testing and commissioning of Cu. Conductor power cable PVC insulated PVC sheathed. 1100 V grade armoured cable in existing PVC conduit on walls / false ceiling / roof. Laid in cable tray with end termination's connections, earthing etc. complete as required 3 x 1.5 sq. mm			
	Service Item 270: Unit basic rate in words _____			
280	7006491 ELECTRICAL CABLE CU. CAB 3x2.5sqmm	260	M (Meter)	
	CABLE LAYING Supply, laying, testing and commissioning of Cu. Conductor power cable PVC insulated PVC sheathed. 1100 V grade armoured cable in existing PVC conduit on walls / false ceiling / roof. Laid in cable tray with end termination's connections, earthing etc. complete as required 3 x 2.5 sq. mm			
	Service Item 280: Unit basic rate in words _____			
290	7006492 ELECTRICAL CABLE CU. CAB 4x2.5sqmm	550	M (Meter)	
	CABLE LAYING Supply, laying, testing and commissioning of Cu. Conductor power cable PVC insulated PVC sheathed. 1100 V grade armoured cable in existing PVC conduit on			
Page 8 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.



RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	walls / false ceiling /roof. Laid in cable tray with end termination's connections, earthing etc. complete as required 4 x 2.5 sq. mm			
	Service Item 290: Unit basic rate in words _____			
300	7006495 ELECTRICAL CABLE CU. CAB 4x10 sq. mm	20	M (Meter)	
	CABLE LAYING Supply, laying, testing and commissioning of Cu. Conductor power cable PVC insulated PVC sheathed. 1100 V grade armoured cable in existing PVC conduit on walls / false ceiling /roof. Laid in cable tray with end termination's connections, earthing etc. complete as required 4 x10 sq. mm			
	Service Item 300: Unit basic rate in words _____			
310	7006543 ELECTRICAL CABLE FLP GLAND 3 x 1.5 sq. m	2	EA (each)	
	CABLE LAYING Supplying flame proof double comp cable gland with adaptor if required (Baliga make or equivalent approved) conforming to IS 2148 suitable for following cable size : 3 x 1.5 sq. mm			
	Service Item 310: Unit basic rate in words _____			
320	7006546 ELECTRICAL CABLE FLP GLAND 3 x 2.5 sq. m	24	EA (each)	
	CABLE LAYING Supplying flame proof double comp cable gland with adaptor if required (Baliga make or equivalent approved) conforming to IS 2148 suitable for following cable size : 3 x 2.5 sq. mm			
	Service Item 320: Unit basic rate in words _____			
330	7006547 ELECTRICAL CABLE FLP GLAND 4 x 2.5 sq. m	24	EA (each)	
	CABLE LAYING Supplying flame proof double comp cable gland with adaptor if required (Baliga make or equivalent approved) conforming to IS 2148 suitable for following cable size : 4 x 2.5 sq. mm			
<b>Page 9 of 44</b>		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number :6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	Service Item 330: Unit basic rate in words _____			
340	7006589 ELECTRICAL EARTH . CU PLATE	1	EA (each)	
	Supply, installation, testing and commissioning of Earthing station with copper plate earth electrode with copper plate 600 x 600 x 3mm size and 3m deep filling with alternate layers of charcoal and salt and connection arrangements with earth strips,including watering arrangement.BM chamber with CI cover as per drawing No. ES.95.04.008B.  Service Item 340: Unit basic rate in words _____			
350	7006590 ELECTRICAL EARTH . INCL BM CHAMBER	10	EA (each)	
	Providing pipe earthing station as per drawing No. ES.95.04.008A including making BM chamber with CI cover and arrangement for watering (For light pole and dispensing pump earthing)  Service Item 350: Unit basic rate in words _____			
360	7006591 ELECTRICAL EARTH . 8 SWG GI Wire	375	M (Meter)	
	Supply and erection of GI/copper wire/strip for loop earthing in pipe/earth/walls with connection etc. complete as required and of following size. 8 SWG GI Wire  Service Item 360: Unit basic rate in words _____			
370	7006592 ELECTRICAL EARTH . 25 x 4 sq.mm GI Stri	120	M (Meter)	
	Supply and erection of GI/copper wire/strip for loop earthing in pipe/earth/walls			
Page 10 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	with connection etc. complete as required and of following size. 25 x 4 sq.mm GI Strip			
	Service Item 370: Unit basic rate in words _____			
380	7006593 ELECTRICAL EARTH . 25 x 3 sq.mm Cu. STR	15	M (Meter)	
	Supply and erection of GI/copper wire/strip for loop earthing in pipe/earth/walls with connection etc. complete as required and of following size. 25 x 3 sq.mm copper strip			
	Service Item 380: Unit basic rate in words _____			
390	7006597 ELECTRICAL . . CONTROL PANEL MS PLA	2.000	M3 (Cubic meter)	
	Providing, fixing, testing & commissioning control panel of size as per plan and details using 14 / 16 SWG M.S. Plate with double door including powder coating in machine grey colour including arrangements to fix meters switch gears etc. according to plan and detail incl. locking arrangements & handles etc. complete.			
	Service Item 390: Unit basic rate in words _____			
400	7006598 ELECTRICAL . . CU BUSBAR 25X5 MM	3	RM (RUNNING METER)	
	Providing and fixing copper busbar of size 25 mm X 5 mm			
	Service Item 400: Unit basic rate in words _____			
410	7006601 ELECTRICAL . DIGITAL AMMETER 0-100A	1	EA (each)	
	Providing and fixing phase digital type ammeter GEC make or equivalent incl selector switch 0-100Amps			
Page 11 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	Service Item 410: Unit basic rate in words _____			
420	7006604 ELECTRICAL . VOLTMETER 0-500 V DIGITAL	1	EA (each)	
	Providing and fixing 3 phase Digital type Voltmeter (0-500V) GEC make or equivalent incl selector switch _____			
	Service Item 420: Unit basic rate in words _____			
430	7006605 ELECTRICAL . CT FOR AMMETER 150/5 0-100A	3	EA (each)	
	Providing and fixing CT for ammeter. for 0-100Amps _____			
	Service Item 430: Unit basic rate in words _____			
440	7006608 ELECTRICAL . P&F RYB FUSES	1	SET (set)	
	Providing and fixing the following Set of RYB phase indicating lamps transformer type with slide fuses _____			
	Service Item 440: Unit basic rate in words _____			
450	7006612 ELECTRICAL . P&F 2.5/6 SQMM CU	2	EA (each)	
	Providing and fixing the following Internal wiring for control panel in 2.5 Sq.mm & 6 sq.mm Cu. Special wire Fire proof / Flame proof of Polycab or equivalent approved make including FLP lug etc. complete. _____			
	Service Item 450: Unit basic rate in words _____			
460	7006627 ELECTRICAL . S FU 64A TPN SFU	2	EA (each)	
<b>Page 12 of 44</b>		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number :6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	Providing fixing testing commissioning main switch fuse unit with with respective FUSES including connections complete. Stanley make or equivalent 64A TPN SFU			
	Service Item 460: Unit basic rate in words _____			
470	7006630 ELECTRICAL . CHANGEOVER SWITCH 63 Amp	1	EA (each)	
	Providing and fixing testing, commissioning change over switch 63 Amp for provision in electric panel			
	Service Item 470: Unit basic rate in words _____			
480	7006634 ELECTRICAL . RCCB/ELCB 40A TPN ELCB	6	EA (each)	
	Providing and fixing RCCB/ELCB with 100MA tripping current capacity with its MS BOX including connection and testing etc. complete.(INDO KOPP) 40A TPN ELCB			
	Service Item 480: Unit basic rate in words _____			
490	7006635 ELECTRICAL . RCCB/ELCB 40A TWO POLE ELCB	1	EA (each)	
	Providing and fixing RCCB/ELCB with 100MA tripping current capacity with its MS BOX including connection and testing etc. complete.(INDO KOPP) 40A TWO POLE ELCB			
	Service Item 490: Unit basic rate in words _____			
500	7006639 ELECTRICAL . MCB 3 PH 15 AMP	2	EA (each)	
	Providing and fixing miniature circuit breaker [3 phase] of approved quality and make confirming to IS 8828 for following ratings :(INDO KOPP, HAGER, MDS) 15 AMP			
	Service Item 500: Unit basic rate in words _____			
Page 13 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

**RFQ Number :** 6000808384

**Date :** 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
510	7006640 ELECTRICAL . MCB 3 PH 32 AMP	6	EA (each)	
Providing and fixing miniature circuit breaker [3 phase] of approved quality and make confirming to IS 8828 for following ratings :(INDO KOPP, HAGER, MDS) 32 AMP <hr/> Service Item 510: Unit basic rate in words _____				
520	7006642 ELECTRICAL . MCB 3 PH 64 AMP	2	EA (each)	
Providing and fixing miniature circuit breaker [3 phase] of approved quality and make confirming to IS 8828 for following ratings :(INDO KOPP, HAGER, MDS) 64 AMP <hr/> Service Item 520: Unit basic rate in words _____				
530	7006644 ELECTRICAL . MCB SINGLE PH 5 AMP	32	EA (each)	
Providing and fixing miniature circuit breaker [single phase/double pole] of approved quality and make confirming to IS 8828 for following ratings :(INDO KOPP, HAGER, MDS) 5 AMP <hr/> Service Item 530: Unit basic rate in words _____				
540	7006649 ELECTRICAL . MCB 1 PH 1 POLE 5 AMP	12	EA (each)	
Providing and fixing miniature circuit breaker [single phase single pole] of approved quality and make confirming to IS 8828 for following ratings :(INDO KOPP, HAGER, MDS) 5 AMP <hr/> Service Item 540: Unit basic rate in words _____				
550	7006650 ELECTRICAL . MCB 1 PH 1 POLE 15 AMP	10	EA (each)	
Providing and fixing miniature circuit breaker [single phase single pole] of				
<b>Page 14 of 44</b>		<b>Vendor Sign &amp; Stamp</b>		<b>For Bharat Petroleum Corporation Ltd.</b>

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
<p>approved quality and make confirming to IS 8828 for following ratings :(INDO KOPP, HAGER, MDS) 15 AMP</p> <hr/> <p style="text-align: center;">Service Item 550: Unit basic rate in words _____</p>				
560	7006651 ELECTRICAL . MCB 1 PH 1 POLE 32 AMP	1	EA (each)	
<p>Providing and fixing miniature circuit breaker [single phase single pole] of approved quality and make confirming to IS 8828 for following ratings :(INDO KOPP, HAGER, MDS) 32 AMP</p> <hr/> <p style="text-align: center;">Service Item 560: Unit basic rate in words _____</p>				
570	7006693 ELECTRICAL . FITTINGS EXHAUST FANS	2	EA (each)	
<p>S/Fixing following fittings either of Philips,Crompton or GCE made incl. all necessary arrangement to fix the same. Supply, installation and commissioning of exhaust fans suitable for use of 220/240V 50Hz single phase with frame gravity drop louvers clamps etc. complete as required 300sweeps size.</p> <hr/> <p style="text-align: center;">Service Item 570: Unit basic rate in words _____</p>				
580	7006695 ELECTRICAL . FITTINGS CEILING FANS	3	EA (each)	
<p>S/Fixing following fittings either of Philips,Crompton or GCE made incl. all necessary arrangement to fix the same. Supply, installation, testing and commissioning of 1400mmsweep 220V, 50Hz AC ceiling fan including providing fan hook suspension rod 300mm long connections, earthing electronic dimmer type regulators etc. complete as required.</p> <hr/> <p style="text-align: center;">Service Item 580: Unit basic rate in words _____</p>				
590	7006726 ELECTRICAL . . S/W LIGHT FAN POINTS	28	EA (each)	
<p>Supply of material and wiring for light /fan point with 3/20 copper conductor, PVC</p>				

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	insulated 650 V grade ISI wires in heavy duty ISI 20 mm PVC conduit laid in existing tray / on wall / in ceilings / floor complete with required plate switches / ceiling rose /			
	Service Item 590: Unit basic rate in words _____			
600	7006731 ELECTRICAL . MODULAR SWITCH FR 1 WAY	2	EA (each)	
	Supply and fixing of modular switch frame and accessories as per details Roma/Crabtree/Sapphire make or equivalent including flush metal boxes / surface mounting boxes plate etc complete as per manufacturers specification and Engineer in charge. 1 way modular frame			
	Service Item 600: Unit basic rate in words _____			
610	7006732 ELECTRICAL . MODULAR SWITCH FR 2WAY	7	EA (each)	
	Supply and fixing of modular switch frame and accessories as per details Roma/Crabtree/Sapphire make or equivalent including flush metal boxes / surface mounting boxes plate etc complete as per manufacturers specification and Engineer in charge. 2 way modular frame			
	Service Item 610: Unit basic rate in words _____			
620	7006733 ELECTRICAL . MODULAR SWITCH FR 3WAY	4	EA (each)	
	Supply and fixing of modular switch frame and accessories as per details Roma/Crabtree/Sapphire make or equivalent including flush metal boxes / surface mounting boxes plate etc complete as per manufacturers specification and Engineer in charge. 3 way modular frame			
	Service Item 620: Unit basic rate in words _____			
630	7006734 ELECTRICAL . MODULAR SWITCH FR 4WAY	3	EA (each)	
<b>Page 16 of 44</b>		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.



RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	Supply and fixing of modular switch frame and accessories as per details Roma/Crabtree/Sapphire make or equivalent including flush metal boxes / surface mounting boxes plate etc complete as per manufacturers specification and Engineer in charge. 4 way modular frame			
	Service Item 630: Unit basic rate in words _____			
640	7006735 ELECTRICAL . MODULAR SWITCH FR 6WAY	11	EA (each)	
	Supply and fixing of modular switch frame and accessories as per details Roma/Crabtree/Sapphire make or equivalent including flush metal boxes / surface mounting boxes plate etc complete as per manufacturers specification and Engineer in charge. 6 way modular frame			
	Service Item 640: Unit basic rate in words _____			
650	7006740 ELECTRICAL . MODULAR SWITCH 6AMP	28	EA (each)	
	S/F Modular Switch- Roma / crabtree or equivalent 6 Amp Modular Switch			
	Service Item 650: Unit basic rate in words _____			
660	7006746 ELECTRICAL . WIRING CONCEALED PLUG3/20 C	14	EA (each)	
	Providing concealed wiring for for plug point incl. socket with 3/20PVC insulated copper conductor wire of approved make and quality in 20mm PVC heavy duty conduit pipe with all fittings like holders switches, wooden blocks, boards etc.			
	Service Item 660: Unit basic rate in words _____			
670	7006757 ELECTRICAL . . P/F 15A PLUG 15A SWI	2	EA (each)	
	Providing and fixing 15A plug point with 4 Sq.mm single core copper conductor, PVC insulated 650 V grade wires in heavy duty ISI 20 mm PVC conduit pipe laid in existing tray / on walls with 5A / 15A socket of approved make like Anchor etc., 15A			
Page 17 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	plate switch complete.			
	Service Item 670: Unit basic rate in words _____			
680	7006758 ELECTRICAL . . P/F 15A PLUG INDUSTR	2	EA (each)	
	Providing and fixing 15A plug point with 4 Sq.mm single core copper conductor, PVC insulated 650 V grade wires in heavy duty ISI 20 mm PVC conduit pipe laid in existing tray / on walls with industrial type plug point of approved make.			
	Service Item 680: Unit basic rate in words _____			
690	7006765 ELECTRICAL . HD PVC CONDUIT 50MM DIA	125	RM (RUNNING METER)	
	Supplying and laying ISI heavy duty 6 kg/cm2 PVC conduit / pipe with accessories and hardware complete as required. in wall / floors, ceilings, false ceilings etc (Prakash / Triputi / Kishan etc.) PVC pipe 50 mm dia			
	Service Item 690: Unit basic rate in words _____			
700	7006767 ELECTRICAL . HD PVC CONDUIT 100MM DIA	250	RM (RUNNING METER)	
	Supplying and laying ISI heavy duty 6 kg/cm2 PVC conduit / pipe with accessories and hardware complete as required. in wall / floors, ceilings, false ceilings etc (Prakash / Triputi / Kishan etc.) PVC pipe 100 mm dia			
	Service Item 700: Unit basic rate in words _____			
710	7006773 ELECTRICAL . FITTINGS ELEC FAN REG	3	EA (each)	
	P & F of following fitting of Anchor or approved make e) Electronic Fan regulator			
	Service Item 710: Unit basic rate in words _____			
Page 18 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number :6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
720	7006774 ELECTRICAL . S/D/F FOLL RUBBER MAT	1	EA (each)	
Supply,delivery & fixing of the following: Insulating rubber matting 6mm thk 11KV grade size 1mx2m conforming to IS -5424/1969 to cover the front of main LT panel.				
Service Item 720: Unit basic rate in words _____				
730	7006776 ELECTRICAL . S/D/F FOLL DANGER PLATE	1	EA (each)	
Supply,delivery & fixing of the following: Danger Plate 415 V/ Caution Board, 200x150mm)				
Service Item 730: Unit basic rate in words _____				
740	7006777 ELECTRICAL . S/D/F FOLL SHOCK CHART	1	EA (each)	
Supply,delivery & fixing of the following: Shock Treatment Chart				
Service Item 740: Unit basic rate in words _____				
750	7008102 ELECTRICAL . . ELECTRIC PANEL STPS	2	EA (each)	
Fixing/Shifting of I/Q Box and control Box electrical panel incl. Connecting all cables, glands etc. & making re-connections at place. Jobs also incl. Commissioning &fixing of panel as reqd. incl. Cost of material & labour etc. complete.				
Service Item 750: Unit basic rate in words _____				
760	7006796 EXC ORD SOIL UPTO 1.5 M	440.000	M3 (Cubic meter)	
<b>Page 19 of 44</b>		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	EXCAVATION Excavation in all kinds of soil such as black cotton, silt, earth; murrum; gravel; kankar; boulders; etc. excluding soft and hard rock and carting away the excavated earth to an unobjectionable area upto 100 Mts.from plot boundary or stacking rubble or spreading and leveling within the site as the case may be back filling in layers of 150mm thick including compacting the trenches with excavated earth free from organic matters; stones; sharp edged material; etc; complete. EXC SOIL UPTO1.5 M			
	Service Item 760: Unit basic rate in words _____			
770	7006797 EXC ORD SOIL FROM 1.5 TO 3M	95.000	M3 (Cubic meter)	
	EXCAVATION Excavation in all kinds of soil such as black cotton, silt, earth; murrum; gravel; kankar; boulders; etc. excluding soft and hard rock and carting away the excavated earth to an unobjectionable area upto 100 Mts.from plot boundary or stacking rubble or spreading and leveling within the site as the case may be back filling in layers of 150mm thick including compacting the trenches with excavated earth free from organic matters; stones; sharp edged material; etc; complete. EXC SOIL 1.5-3M			
	Service Item 770: Unit basic rate in words _____			
780	7006833 FENCING . CHAINLINK 1.35 M HIGH	129	RM (RUNNING METER)	
	FENCING/BOUNDARY WALL Supplying and erecting chainlink fencing with 2nos. 4mm GI straining wire on the following heights of angle iron posts at approximately 2.5m centre to centre embedded in CC 1:3:6as per our standard drawing no E.1S.01.001 incl. painting vertical post with 2coats each of Red oxide and aluminium paint. 1.35m high			
	Service Item 780: Unit basic rate in words _____			
790	7006845 FILLING MOORUM VIBRO FROM OUTSIDE	115.000	M3 (Cubic meter)	
	EARTH FILLING Supplying & filling approved quality murrum in 300 mm thick layer well compacted after sprinkling required quantity of water. The consolidation shall be done using vibratory roller. Measurement shall be taken only after compaction. Upto a max of 350Cum Brought from outside			
Page 20 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	Service Item 790: Unit basic rate in words _____			
800	7006849 FILLING EARTH FROM O/S WITH HAND	80.000	M3 (Cubic meter)	
	EARTH FILLING Back filling with approved quality earth in 150 mm thick layers well compacted after sprinkling required quantity of water upto a max of 500Cum Brought from outside Consolidate with Hand rammer Service Item 800: Unit basic rate in words _____			
810	7006886 FLOOR TILE . NON SKID 7.5 Tk	39	M2 (Square meter)	
	FLOORING Providing and Fixing non-skid first quality ceramic tiles 7.5mm of SPARTEK/BELL/KAJARIA or of approved equivalent make in approved colour with cement mortar bedding in flooring or skirting including filling of joints with white cement mixed with colored pigment to match the tile colour. Service Item 810: Unit basic rate in words _____			
820	7006887 FLOOR TILE . EUROCON	29	M2 (Square meter)	
	FLOORING Supplying and fixing EURO-CON tiles or equivalent with necessary CM 1:3 bedding including chipping the base as necessary, curing etc. complete. Service Item 820: Unit basic rate in words _____			
830	7006890 FLOOR TILE MARBO For size 600 x 600mm	23	M2 (Square meter)	
	FLOORING Providing & laying granite finish tile 'MARBONITE' or any other approved make set in cement mortar bedding in flooring or skirting or dadoo including filling of joints with white cement mixed with colored pigment to match the tile colour. For size 600 x 600mm Service Item 830: Unit basic rate in words _____			
Page 21 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	Service Item 830: Unit basic rate in words _____			
840	7006891 FLOOR USING CC 1:2:4 . IPS 50 MM	45	M2 (Square meter)	
	FLOORING Providing and Laying IPS 50 mm thick in cement concretel:2:4 mix for flooring and dado including finishing the top in neat cement slurry and marking the false square or as directed.			
	Service Item 840: Unit basic rate in words _____			
850	7006892 FLOOR USING STONE 20-25 MM THK KOTA	13.500	M2 (Square meter)	
	FLOORING Providing and laying Polished Kota stone flooring /skirting as per required size of thickness 20-25 mm in 1:4 cement mortar including curing polishing etc. complete.			
	Service Item 850: Unit basic rate in words _____			
860	7006896 FLOOR USING STONE GRANITE 18 TK	16.500	M2 (Square meter)	
	FLOORING Supplying and fixing 18mm thick (minimum) mirror polished Granite stone of approved quality for flooring/sills/dadoo and pump island including cutting in required shape & size including bedding and backing as directed.			
	Service Item 860: Unit basic rate in words _____			
870	7006939 FOUNDN . . RUBBLE SOLING	25.000	M3 (Cubic meter)	
	Providing and laying Hand Packed Rubble Cut Stone Soling of size 60 to 80mm in flooring / driveway duly consolidated. approved quality, as close as possible,,,hand packing with stone chippings to fill the voids, laying murrum, hand ramming, watering, well consolidating complete as per			
Page 22 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number :6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	specifications, drawings and instructions including preparation of bed and dressing the same to proper level etc complete.			
	Service Item 870: Unit basic rate in words _____			
880	7006946 FOUNDN . PCC WITH 20MM METAL 1:2:4	10.500	M3 (Cubic meter)	
	FOUNDATION; PLINTH; SUPERSTRUCTURE Providing & laying cement concrete at all height/depth using 20mm metal incl. necessary shutting form work & curing for a period of 14 days Removing of centering ,shuttering, scaffolding shall be done carefully without such shock or vibration as would damage the concrete in foundation and or in plinth. 1:2:4 mix.			
	Service Item 880: Unit basic rate in words _____			
890	7006947 FOUNDN . PCC WITH 20MM METAL 1:3:6	149.750	M3 (Cubic meter)	
	FOUNDATION; PLINTH; SUPERSTRUCTURE Providing & laying cement concrete at all height/depth using 20mm metal incl. necessary shutting form work & curing for a period of 14 days Removing of centering ,shuttering, scaffolding shall be done carefully without such shock or vibration as would damage the concrete in foundation and or in plinth. 1:3:6 mix.			
	Service Item 890: Unit basic rate in words _____			
900	7006948 FOUNDN . RCC 1:1.5:3 Mix	97.600	M3 (Cubic meter)	
	FOUNDATION; PLINTH; SUPERSTRUCTURE Providing and laying reinforced cement concrete using reinforcement and 20mm metal incl. shuttering form work and curing for a period of 14 days. Removing of centering, shuttering, shoring scaffolding shall be done carefully without such shock or vibration as would damage the concrete in foundation; lintel; plinth; column; beam ,slab etc. (excluding cost of reinforcement) 1:1.5:3 mix.			
	Service Item 900: Unit basic rate in words _____			
Page 23 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
910	7006949 FOUNDN . RCC 1:2:4 mix	24.250	M3 (Cubic meter)	
<p>FOUNDATION; PLINTH; SUPERSTRUCTURE Providing and laying reinforced cement concrete using reinforcement and 20mm metal incl. shuttering form work and curing for a period of 14 days. Removing of centering, shuttering, shoring scaffolding shall be done carefully without such shock or vibration as would damage the concrete in foundation; lintel; plinth; column; beam ,slab etc.(excluding cost of reinforcement) 1:2:4 mix.</p> <p>Service Item 910: Unit basic rate in words _____</p>				
920	7006950 PIPE . U/G SUCTION C 50 PIP UNDER ORD SO	23	RM (RUNNING METER)	
<p>PIPELINES AND FITTINGS: Supplying and laying U/G and A/G ERW 'C' class pipe 50mmdia for suction/vent/Dip conforming to IS 1239-1979(preferably Tata make) to the required slope and alignment with heavy duty fittings like elbows, tees, bends, unions,couplings, reducers, valves etc.of ISI mark as directed by Site Eng. incl. pressure testing at 3.6 kg/ cm2 or 10Kg/cm2 job also includes excavation of trench, back filling for making the driveway in original after laying pipeline and doping U/G pipeline with two coats of bituminous primer and3mm thick (dry thickness) Shalimar tar plastic or painting A/G pipeline with two coats each of Red Oxide primer and approved quality/shade/make enamel paint after cleaning and scrapping the pipeline to bare metal. This also includes fixing of supplied valves and making necessary connections to pump and/ or tank as the case may be Under ordinary soil</p> <p>Service Item 920: Unit basic rate in words _____</p>				
930	7006956 PIPE . S/L FILL C 75 PIPE UNDER ORD SOIL	24	RM (RUNNING METER)	
<p>PIPELINES AND FITTINGS: Supplying and laying U/G and A/G ERW 'C' class pipe 75mmdia fill line conforming to IS 1239-1979 (preferably Tatamake) to the required slope and alignment with heavy duty fittings like elbows, tees, bends, unions, couplings,reducers etc. valves etc.of ISI mark as directed by Site Engineer. incl. pressure testing job also includes excavation of trench, back filling for making the driveway in original after laying pipeline and doping U/G pipeline with two coats of bituminous primer and 3mmthick (dry thickness) Shalimar tar plastic or painting A/G pipeline with two coats each of Red Oxide primer and approved quality/shade/make enamel paint after cleaning and scrapping the pipeline to bare metal. This also includes fixing of supplied valves and making necessary connections to pump and/ or tank as the case may be Under ordinary soil</p>				
Page 24 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.



RFQ Number :6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	Service Item 930: Unit basic rate in words _____			
940	7006972 PIPE . MS SEAMLESS 50 UNDER ORD SOIL	110	RM (RUNNING METER)	
	PIPELINES AND FITTINGS: Supplying, installing, laying, welding & testing M.S. seamless pipeline 50mm dia for suction/vent/Dip confirming to ASTM 106 Gr. B schedule 40 for suction / fill & ventpipes in proper slopes and level incl. Fitting of flanges elbows for end fittings etc. testing the pipelines to a pressure of 10 kg/cm2and excavation, backfilling and redoing the surface in original condition complete. Under ordinary soil			
	Service Item 940: Unit basic rate in words _____			
950	7007019 PIPE . CS SEAMLESS ELBOW 50 NB DIA	16	EA (each)	
	PIPELINES AND FITTINGS: Supply of C.S. seamless fitting confirming to ASTM A234 Gr.WP B class 150-90 deg. Short radius elbows. 50 NB dia.			
	Service Item 950: Unit basic rate in words _____			
960	7007025 PIPE . SUPPLY OF FLANGES 50 NB DIA	38	EA (each)	
	PIPELINES AND FITTINGS: Supply of flanges confirming to ASTM A105 class 150 ANSIB 16.5 - suc.40. 50 NB dia.			
	Service Item 960: Unit basic rate in words _____			
970	7007031 PIPE . TEFLON SHEET PACKING 50 NB DIA	19	EA (each)	
	PIPELINES AND FITTINGS: Teflon sheet packing for flange joints. 50 NB dia.			
	Service Item 970: Unit basic rate in words _____			
Page 25 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
980	7007032 PIPE . TEFLON SHEET PACKING 80 NB DIA	2	EA (each)	
PIPELINES AND FITTINGS: Teflon sheet packing for flange joints. 80 NB dia.				
Service Item 980: Unit basic rate in words _____				
990	7007036 PIPE . S,F AND PAINT 50 MM DIP CAP	2	EA (each)	
PIPELINES AND FITTINGS: Supplying, fixing and painting as per Company's colour scheme 50 mm dip cap assembly and cap of Aluminium with locking arrangement				
Service Item 990: Unit basic rate in words _____				
1000	7007037 PIPE . S,F AND PAINT 75MM FILL CAP	2	EA (each)	
PIPELINES AND FITTINGS: Supplying, fixing and painting as per Company's colour scheme 75 mm fill cap assembly and cap of Aluminium with locking arrangement				
Service Item 1000: Unit basic rate in words _____				
1010	7007045 PIPE . S,F AND PAINT 50 MM BALL VALVE	2	EA (each)	
PIPELINES AND FITTINGS: Supplying, fixing and painting as per Company's colour scheme 50 mm NB Stainless steel ball valve Audco or equivalent				
Service Item 1010: Unit basic rate in words _____				
1020	7007053 PIPE . . S/FAL. ROUND COLLAR	2	EA (each)	
PIPELINES AND FITTINGS: Supplying and fixing Aluminium round collar to dip rod and making it floating type excl. extending dip pipe / cutting the dip rod as necessary.				
Page 26 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	Service Item 1020: Unit basic rate in words _____			
1030	7007072 PIPE . MANHOLE COVER MODIFY STP	2	EA (each)	
	PIPELINES AND FITTINGS: Modification of Manhole cover as per our std. including the cost of all materials for installation of Submersible pump Service Item 1030: Unit basic rate in words _____			
1040	7007096 PIPE . BLACK TEE SUPPLY 50 MM	4	EA (each)	
	PIPELINES AND FITTINGS: Supply only of black tee (Heavy quality) conforming to IS1239 /1979 (preferably TATA make). All should be tested at 3.6 Kg/Cm2 before use. 50 mm Service Item 1040: Unit basic rate in words _____			
1050	7007166 PAINT WW . PLASTIC EMULSION 2 COATS	232	M2 (Square meter)	
	WHITE WASHING / PAINTING : Preparing surface and painting with Plastic Emulsion of approved make, shade and quality in all heights of walls, ceiling, sun sheds fins etc. incl. providing scaffolding, cleaning, curing and supply of all materials and labour complete. 2 coats Service Item 1050: Unit basic rate in words _____			
1060	7007177 PAINT WW . SPL ANTI FUNGAL PAINT	553	M2 (Square meter)	
	WHITE WASHING / PAINTING : Scrapping surfaces, steel doors, windows with wire brush or cleaning masonry surface with coir brush or preparing the surface and applying following paints of approved make, shaquality incl. Supply of all materials and labour with two coats Anti - Fungal, Anti - Algai Exterior Paint (Apolite Apex Exterior Paint) of Asian Paints of or equivalent approved shade, in two coats as per the instructions of the manufacturers; giving uniform shade etc. Service Item 1060: Unit basic rate in words _____			
Page 27 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	Service Item 1060: Unit basic rate in words _____			
1070	7007216 PAINT WW . . SUMP COVER PAINTING	33	M2 (Square meter)	
	WHITE WASHING / PAINTING : Wire brushing, scrapping, cleaning both sides of Sump cover and applying two coats each of approved quality/make/shade Red Oxide primer and Synthetic Enamel paint complete incl.cost of labour and paint			
	Service Item 1070: Unit basic rate in words _____			
1080	7007186 PAINT WW . STEEL DOOR 2 COAT CEMENT PRIM	820	M2 (Square meter)	
	WHITE WASHING / PAINTING : Scrapping surfaces, steel doors, windows with wire brush or cleaning masonry surface with coil brush or preparing the wooden surfaces and applying following paints of approved make/shade/quality incl. Supply of all materials 2 coats of cement primer			
	Service Item 1080: Unit basic rate in words _____			
1090	7007260 DWAY . . LAYING 40/60 MM META	18.250	M3 (Cubic meter)	
	ROAD WORK Providing and laying 60mm metal and 40mm metal specified to a thickness and compacting the same to the engineer's satisfaction with a roller weighing not less than 10 ton			
	Service Item 1090: Unit basic rate in words _____			
1100	7007262 DWAY . . RUBBLE SOLING 225TK	2,560	M2 (Square meter)	
	Providing and laying SOLING 225mm thick (compacted thickness) using boulders of size Hand Packed Rubble Cut Stone Soling of size 80 to 150mm in flooring / driveway duly consolidated. approved quality, as close as possible,,,hand packing with stone chippings to fill the voids, laying murrum, ramming,			
Page 28 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number :6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	watering, well consolidating with 10 MT roller complete as per specifications, drawings and instructions including preparation of bed and dressing the same to proper level etc complete..			
	Service Item 1100: Unit basic rate in words _____			
1110	7007317 ROOF STEEL . SECTIONS	2,825.000	KG (Kilogram)	
	ROOFING Supply/fabricating/erecting the Steel Section and in rolled steel sections like R.S.J.; angles; Tees; channels etc and plates; square or rectangular rods.TATA or SAIL make complete.including providing 2 coats of redoxide/zinc chromate pink primer. (for less than ISA 50,locally available BIS certified sections to be used)			
	Service Item 1110: Unit basic rate in words _____			
1120	7007321 SANITARY . WC PEDESTAL TYPE	2	EA (each)	
	SANITARY Providing and fixing vitreous china water closet Wall Pedestal Type (European type) of approved colour having back inlet P trap with seat and lid with C.P. brass hinges and rubble buffers; supporting cast iron chair with bolts. (if required)			
	Service Item 1120: Unit basic rate in words _____			
1130	7007325 SANITARY . WC PVC FLUSHING CI	2	EA (each)	
	SANITARY Providing & fixing PVC low level flushing cistern of ISI mark; 10 lit capacity; with CI brackets; 32 mm concealed PVC flush pipe brass ball cock with PVC ball; 15 mm CP brass stop cock; 15mm PVC inlet connection; 15 mm PVC overflow pipe including connection to water closet etc. complete.			
	Service Item 1130: Unit basic rate in words _____			
1140	7007331 SANITARY . . FLAT BACK URINAL	1	EA (each)	
Page 29 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	SANITARY Providing and fixing appd. make white glazed flat back or wall corner urinal wall mounted type including all necessary fixtures like inlet pipe and 12.5mm CP cock outlet CP bottle trap brass water sprayer set., complete.			
	Service Item 1140: Unit basic rate in words _____			
1150	7007334 SANITARY . WASH BASIN COLOR 450 X 300 NO	2	EA (each)	
	SANITARY Providing and fixing 450 x 300mm size color vitreous china wash basin of CERA or other approved make & shade suitable for mounting on CI brackets, 32mm dia. CP brass waste coupling of standard pattern, 32 mm dia .CP brass bottle trap and unions, 32mm dia PVC waste pipe, C.P. brass chain with plug and 15mm CP brass pillar tap, CP brass stop tap with PVC connection, complete.			
	Service Item 1150: Unit basic rate in words _____			
1160	7007337 SANITARY . . MIRROR 600x450MM	2	EA (each)	
	SANITARY Providing and fixing 600 x 450mm bevelled edge mirror of superior glass of approved quality with 6mm thick asbestos cement sheet ground fixed to wooden cleats with CP brass screws and washers complete as required.			
	Service Item 1160: Unit basic rate in words _____			
1170	7007338 SANITARY . . SOAP DISPENSER	2	EA (each)	
	SANITARY Providing and fixing SS /CP Brass soap dispenser of superior quality.			
	Service Item 1170: Unit basic rate in words _____			
1180	7007350 SANITARY . . 100MM EARTHWARE GULL	2	EA (each)	
	SANITARY Supplying and fixing earthware gully trap 100mm size with CI grating on top incl. constructing suitable masonry chamber and plastering etc. complete.			
Page 30 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	Service Item 1180: Unit basic rate in words _____			
1190	7007351 SANITARY . SCI NAHANI TRAP 75mm	5	EA (each)	
	SANITARY Providing and fixing sand cast iron Nahani trap of self cleansing design with sand cast iron or C.P. brass grating with or without vent arm; of the below mentioned sizes for inlet and outlet; complete including cost of cutting and making good the walls and floors wherever if required. 75mm			
	Service Item 1190: Unit basic rate in words _____			
1200	7007354 SANITARY . NRV FOR WATER TANK 25 mm	1	EA (each)	
	SANITARY Supplying and fixing Non Return Valve for water tank. Leader make 25mm			
	Service Item 1200: Unit basic rate in words _____			
1210	7007369 SANITARY . . SOAK PIT 2.5DIA 3DEE	1	EA (each)	
	Construction of 2.5 m dia & 3m deep soak pit incl.with top slab as above as per drawing no. E.1A.01.014A.			
	Service Item 1210: Unit basic rate in words _____			
1220	7007375 SANITARY . . SEPTIC TANK 50 USERS	1	EA (each)	
	SANITARY Constructing 250 mm thk brick masonry walls for septic tank as per standard drawing for 50 users incl.excavation,sand filling,cement concrete foundn,plastering cm (1:3) of internal walls with water proofing compound,plastering cm 1:4 external wall,on top & sides upto 230 mm below finished formation ground level and also incl. CI manhole cover over septic tank,inlet / outlet chambers,3 m long 56 mm dia AC vent pipe with AC cover / fixed to the roof slope of the septic tank.			
Page 31 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number :6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	Service Item 1220: Unit basic rate in words _____			
1230	7007376 SANITARY . INSPECTION CHAMBER 450x450	23	EA (each)	
	SANITARY Constructing brick masonry inspection chamber sizes as given below upto 0.60 M average depth in cement mortar 1:6, cement concrete 1:3:6 75mm thick in foundation, cement conc.1:2:4 50mm thick benching,12mm thick cement plaster 1:2 with floating coat of 1mm thk. of neat cement,RCC 1:2:4 slab 100 mm thk CC topping 50mm thk. size 450 x 450 mm			
	Service Item 1230: Unit basic rate in words _____			
1240	7007377 SANITARY . INSPECTION CHAMBER 600x600	6	EA (each)	
	SANITARY Constructing brick masonry inspection chamber sizes as given below upto 0.60 M average depth in cement mortar 1:6, cement concrete 1:3:6 75mm thick in foundation, cement conc.1:2:4 50mm thick benching,12mm thick cement plaster 1:2 with floating coat of 1mm thk. of neat cement,RCC 1:2:4 slab 100 mm thk CC topping 50mm thk. size 600 x 600 mm			
	Service Item 1240: Unit basic rate in words _____			
1250	7007382 SANITARY . HD CI COVER FOR MH 600x600	3	EA (each)	
	SANITARY S/F heavy duty C.I. cover & frame suitable to the following sizes inspection chambers,weight as per BIS Specifications painted with 3 coats of black bitumastic superior paint / enamel paint as approved. size 600 x 600 mm			
	Service Item 1250: Unit basic rate in words _____			
1260	7007391 SANITARY . BRASS TOWEL RAILS 600MM LONG	2	EA (each)	
	SANITARY P&F in position best Indian make 25 dia CP brass adjustable towel rails fixed in with rawl plugs embedded in walls with CP brass screws complete in all			
Page 32 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.



RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	respect incl. Cutting & making good the walls etc. 600 mm long			
	Service Item 1260: Unit basic rate in words _____			
1270	7007393 SANITARY . GATE VALVE 25MM DIA	2	EA (each)	
	SANITARY Providing and fixing screwed gate valve with CI wheel of approved quality. 25 mm nominal bore			
	Service Item 1270: Unit basic rate in words _____			
1280	7007402 SANITARY . PVC SWR PIPE DRAIN 75MM DIA	70	RM (RUNNING METER)	
	SANITARY Providing and fixing PVC injection moulded PVC 'SWR' pipe for external drainage including fittings; cowls & fixing pipe with clamps etc. 75 mm dia			
	Service Item 1280: Unit basic rate in words _____			
1290	7007403 SANITARY . PVC SWR PIPE DRAIN 110MM DIA	30	RM (RUNNING METER)	
	SANITARY Providing and fixing PVC injection moulded PVC 'SWR' pipe for external drainage including fittings; cowls & fixing pipe with clamps etc. 110 mm dia.			
	Service Item 1290: Unit basic rate in words _____			
1300	7007407 SANITARY . UPVC PIPES 160MM 4 KG SQCM	32	RM (RUNNING METER)	
	SANITARY Providing and laying unplasticised polyvinyl chloride (UPVC) pipes conforming to IS:4985 including all necessary fittings conforming to IS/BS 4514 and other accessories including connections etc. complete as per drawings. 160 mm dia 4 kg Sq.cm			
	Service Item 1300: Unit basic rate in words _____			
Page 33 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
1310	7007423 SANITARY . HD PVC PIPE 15MM DIA	30	RM (RUNNING METER)	
<p>SANITARY Providing and fixing High density PVC pipes with PVC fittings and clamps. Complete as per drawings including cutting and making good the walls and floor wherever required.(internal work) 15mm nominal bore</p> <p>Service Item 1310: Unit basic rate in words _____</p>				
1320	7007425 SANITARY . HD PVC PIPE 25MM DIA	25	RM (RUNNING METER)	
<p>SANITARY Providing and fixing High density PVC pipes with PVC fittings and clamps. Complete as per drawings including cutting and making good the walls and floor wherever required.(internal work) 25mm nominal bore</p> <p>Service Item 1320: Unit basic rate in words _____</p>				
1330	7007427 SANITARY . HD PVC PIPE 40MM DIA	25	RM (RUNNING METER)	
<p>SANITARY Providing and fixing High density PVC pipes with PVC fittings and clamps. Complete as per drawings including cutting and making good the walls and floor wherever required.(internal work) 40mm nominal bore</p> <p>Service Item 1330: Unit basic rate in words _____</p>				
1340	7007428 SANITARY . BRASS STOP COCK 12MM	8	EA (each)	
<p>SANITARY Supplying and fixing heavy type CP brass stop cock (Esc or equiv.) 12 mm size</p> <p>Service Item 1340: Unit basic rate in words _____</p>				
1350	7007441 SANITARY . PVC COWL 75MM DIA	10	EA (each)	
<p>Page 34 of 44</p>		<p>Vendor Sign &amp; Stamp</p>		<p>For Bharat Petroleum Corporation Ltd.</p>

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	SANITARY Supplying and fixing PVC/CI cowl for sanitary vent pipe 75mm dia			
	Service Item 1350: Unit basic rate in words _____			
1360	7007449 SANITARY . SINTEX TANKS 1000 ltrs. capac	1	EA (each)	
	SANITARY Supplying and fixing Syntex/infra water tanks incl. cost of necessary fittings for inflow/outflow/overflow of water excl. the cost of ladder. 1000 ltrs. capacity			
	Service Item 1360: Unit basic rate in words _____			
1370	7007475 SIGN MONOLITH . FOUNDATION	1	EA (each)	
	EMBLEM POLE & SIGNAGES Providing foundation for monolith as per std drg. and specification including cost of foundation bolts and labour complete			
	Service Item 1370: Unit basic rate in words _____			
1380	7007546 TANK . . S/F GRAPHITE ASB. GA	2	EA (each)	
	MECHANICAL - UNDERGROUND TANKS/PIPELINES Supplying 3 mm thick compressed graphite asbestos gasket for manhole cover.			
	Service Item 1380: Unit basic rate in words _____			
1390	7007552 TANK . . S/F 50 MM VENT HOOD	2	EA (each)	
	MECHANICAL - UNDERGROUND TANKS/PIPELINES Supplying and fitting 50mm vent hood for U/G tank vent pipe comprising of 2 nos. 50mm elbows, 1 no. 50mm nipple with 2 layers of brass mesh of 11 mesh/linear cm as per our standards.			
	Service Item 1390: Unit basic rate in words _____			
Page 35 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
1400	7007553 TANK . . S/F BOLTS & NUTS 16M	110	EA (each)	
MECHANICAL - UNDERGROUND TANKS/PIPELINES Supplying 16mm diameter 50mm length of approved quality and make (GKW) bolts, nuts and washer complete.				
Service Item 1400: Unit basic rate in words _____				
1410	7007572 TANK . LOCKING ARRANGEMENT FILL LINE	2	EA (each)	
MECHANICAL - UNDERGROUND TANKS/PIPELINES Supplying and fixing locking arrangement as per the company's standard specifications Fill line				
Service Item 1410: Unit basic rate in words _____				
1420	7007573 TANK . LOCKING ARRANGEMENT DIP PIPE	2	EA (each)	
MECHANICAL - UNDERGROUND TANKS/PIPELINES Supplying and fixing locking arrangement as per the company's standard specifications Dip pipe				
Service Item 1420: Unit basic rate in words _____				
1430	7007575 TANK . . S/FMS THREADED BOLTS	14	EA (each)	
MECHANICAL - UNDERGROUND TANKS/PIPELINES Supplying and fixing 25mm dia and 1.2 meter long MS threaded bolts with nuts & washers incl. providing 100 X100 X 6mm thick MS base plate for HD arrangement				
Service Item 1430: Unit basic rate in words _____				
1440	7007609 TANK . DOPING PIPELINE 50 MM DIA	110	RM (RUNNING METER)	
MECHANICAL - UNDERGROUND TANKS/PIPELINES Doping of U/G pipeline with 3 coats of Shalimar tank mastic bitumen paint as per specifications and as directed 50mm dia				
Page 36 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	Service Item 1440: Unit basic rate in words _____			
1450	7007611 TANK . BM CHAMBER 1X1X0.9M	4	LS (Lumpsum)	
	MConstructing brick masonry inspection chamber sizes of 230mm thick as given below upto 0.90 M average depth in cement mortar 1:6, cement concrete 1:3:6 75mm thick in foundation, cement conc.1:2:4 50mm thick benching, 12mm thick cement plaster 1:2 with floating coat of 1mm thk. of neat cement. inner size 1.0 x 1.0 x 0.9 m			
	Service Item 1450: Unit basic rate in words _____			
1460	7007620 WATER PROOFING . . CHINA MOSAIC	70	M2 (Square meter)	
	WATER PROOFING Waterproofing using China mosaic on top as per the following specifications. Chipping off top of the deteriorated terrace/slab incl. 150mm of parapet walls upto uniform depth and providing; laying brickbat coba waterproofing the terrace/slab; with an average 100mm.thick concrete of broken brickbats and cement mortar (1:5) in proportions of 2 parts of brick bats to one part of cement mortar; laid in proper slope with vata 150mm at junction of parapet walls and IPS flooring 1:2:4 mix; 30mmthick laid in alternate suitable squares and the joint with bitumen and cleaning the terrace/slab top of all dust loose materials; tamping; finishing and curing complete.			
	Service Item 1460: Unit basic rate in words _____			
1470	7007779 PROV. & FIX. MORBO GRANITE	12	RM (RUNNING METER)	
	Providing and fixing MORBO GRANITE or equivalent approved make tiles on pump pedestal as per NEW RVM standards.			
	Service Item 1470: Unit basic rate in words _____			
Page 37 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	Service Item 1470: Unit basic rate in words _____			
1480	7008136 PUMP . . FITTINGS	4	EA (each)	
	DISPENSING PUMPS FIXING OF ANY SUPPLIED VALVES FOR MPD PUMPS			
	Service Item 1480: Unit basic rate in words _____			
1490	7008143 PUMP . . U-CLAIMP	4	EA (each)	
	DISPENSING PUMPS S/F of U CLAIMPS for shear valve including fixing			
	Service Item 1490: Unit basic rate in words _____			
1500	7008220 TANK . . TANK FIXING RISER PI	2	EA (each)	
	MECHANICAL - UNDERGROUND TANKS/PIPELINES Making modifications in u/g tank manhole cover providing riser pipe in U/G tanks M/H cover for installing Auto level gauge.Overall hight of the riser pipe shall be 40cm and 50mm dia with 50dia flange at the bottom & 100mm wide threading at the top of riser pipe for fixing the probe.Modify the flange ID of riser pipe with Dia of riser pipe by boring .welding of the pipe and flange joint shall be ground so as to ensure proper tightening of the flange with M/H cover.Cost includes consumables material & labour etc.complete.and refixing cover complete			
	Service Item 1500: Unit basic rate in words _____			
1510	7007253	2,470	M2	
Page 38 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	DWAY . WBM 150 MM THICK		(Square meter)	
<p>Supplying and spreading stone aggregate of required size of Grade 1 or Grade2 or Grade3 as per our specification in 2 layers to achieve the required thickness as mentioned below, followed by supplying and spreading 20mm down stone aggregate to fill voids, re-rolling the same with 8 - 10 ton roller, followed by supplying and spreading murrum or quarry dust or approved quality earth, consolidating the same with optimum water moisture till the surface is evenly and densely consolidate to achieve. NOTE : Please note that each layer of stone aggregate has to be consolidated with 8 - 10 ton roller. During the murrum filling, watering should be done per each run of the roller and minimum 5 such runs have to be undertaken on subgrade. During each such sun if any void is observed after watering the same shall be filled using 1:1mix of 20 mm metal of murrum. The spreading of murrum, sprinkling of water, sweeping with a broom and rolling shall continue until the slurry that is formed well after filling the voids formed ahead of the wheels of the moving roller and any undulations in the surface developed due to rolling shall be made good. The rates should be inclusive of all cost of equipment, material, labour etc. 150 mm thick compacted WBM using stone aggregate of size 50- 75 mm</p> <hr/> <p>Service Item 1510: Unit basic rate in words _____</p>				
1520	7007463 SANITARY STEEL WATER TANK RCC HUME PIPE	15	RM (RUNNING METER)	
<p>SANITARY Supplying &amp; laying RCC hume pipe of NP3 class in trenches for drainage/culverts including colors &amp; filling the joints with Shun gasket &amp; cement. 900 mm dia</p> <hr/> <p>Service Item 1520: Unit basic rate in words _____</p>				
<p>Service Tax% _____ VAT% _____ CST% _____</p>				
00020 CONSTRUCTION OF NRO DEVALIYA-FIM ITEMS			03.06.2015	
<p>The item 00020 covers the following services:</p>				
10	7006696 ELECTRICAL . FITTINGS CANOPY LIGHT FIXTU	8	EA (each)	
<p>S/Fixing following fittings either of Philips, Crompton or GCE made incl. all necessary arrangement to fix the same. Fixing supplied light fixtures for canopy</p>				
Page 39 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.

RFQ Number : 6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	<p>false ceiling including suspending the fixture from the top canopy structure with supplied control gear including making electrical connections etc complete as directed.</p> <p>Service Item 10: Unit basic rate in words _____</p>			
20	7006697 ELECTRICAL . FITTINGS MH TO LIGHT POLE	6	EA (each)	
	<p>S/Fixing following fittings either of Philips,Crompton or GCE made incl. all necessary arrangement to fix the same. Fixing the supplied metal halide/SV street luminaires on yard lighting</p> <p>Service Item 20: Unit basic rate in words _____</p>			
30	7008088 ELECTRICAL . . IT&C UPS/CVT/STAB	1	EA (each)	
	<p>Installing , Fixing , Testing &amp; Commissioning Supplied UPS/Stabiliser/CVTs above 10KVA and up to 50KVA stabiliser/UPS</p> <p>Service Item 30: Unit basic rate in words _____</p>			
40	7007582 TANK . INSTALL U/G TANK H/D 15 KL TANK	1	EA (each)	
	<p>MECHANICAL - UNDERGROUND TANKS/PIPELINES Installation of cylindrical underground tank with HD arrangement as per our Std. Drg. in earth pit, after excavation in all kinds of soil, bailing out of water, lowering the tank, levelling and testing the tank hydrostatically with fresh water to a pressure of 0.36kg/cm2 for 2 hrs. painting with 2 coats of PF4 applying Shalimar tar plastic 3 mm thick including cost of paint to exterior surface of the tank, back filling of earth 150 mm, layers including adequate watering, ramming etc. as per std. drawing incl. cleaning of the site, providing 3 mm thick compressed graphite asbestos at manhole cover incl. supply of materials, labour, complete to the satisfaction of Engineer-in-Charge with RCC/masonry kerb wall. 15 KL tank as per std drg no RE.DRG.401</p>			
Page 40 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.



RFQ Number :6000808384

Date : 03.02.2015

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

Item	Material Description	Qty	Unit Delivery date	Unit Basic Rate (in Figures)
	Service Item 40: Unit basic rate in words _____			
50	7007583 TANK . INSTALL U/G TANK H/D 20 KL TANK	1	EA (each)	
	MECHANICAL - UNDERGROUND TANKS/PIPELINES Installation of cylindrical underground tank with HD arrangement as per our Std. Drg. in earth pit, after excavation in all kinds of soil, bailing out of water, lowering the tank, levelling and testing the tank hydrostatically with fresh water to a pressure of 0.36kg/cm2 for 2 hrs. painting with 2 coats of PF4 applying Shalimar tar plastic 3 mm thick including cost of paint to exterior surface of the tank, back filling of earth 150 mm, layers including adequate watering, ramming etc. as per std. drawing incl. cleaning of the site, providing 3 mm thick compressed graphite asbestos at manhole cover incl. supply of materials, labour, complete to the satisfaction of Engineer-in-Charge with RCC/masonry kerb wall. 20 KL tank as per std drg no RE.DRG.402			
	Service Item 50: Unit basic rate in words _____			
60	7007144 PUMP . INSTALLING 2 PX4HMPD	2	EA (each)	
	DISPENSING PUMPS Installing new pump on pedestal incl. providing and fixing foundation bolts in CC 1:1.5:3 and connecting suction, electrical, earthing connections. 2 product 4 hose			
	Service Item 60: Unit basic rate in words _____			
70	7007146 PUMP . INSTALLING STP	2	EA (each)	
	DISPENSING PUMPS Installing new pump on pedestal incl. providing and fixing foundation bolts in CC 1:1.5:3 and connecting suction, electrical, earthing connections. Installing submersible pump on the manhole cover incl. Making necessary alterations to the manhole cover to receive the pump and connecting pressure pipeline ,electrical, earthing connections .			
	Service Item 70: Unit basic rate in words _____			
Page 41 of 44		Vendor Sign & Stamp		For Bharat Petroleum Corporation Ltd.



**TERMS & CONDITIONS**

**Important Notice**

<b>Sr.No</b>	<b>Description</b>
001	Quotation received after due date will not be entertained
002	Your quotation must specify exact amount or percentage discount, Excise, S.T., Charges, Transport, Packing & forwarding, Octroi, etc. as applicable.
003	In case you are unable to quote, kindly send the quotation with a regret for our records. Non-receipt of a regret will adversely affect your vendor rating.
004	No quotation will be accepted without your rubber stamp and signature.
005	Your quotation must be strictly in enclosed envelope indicating Collective RFQ No., RFQ No. and due date.
006	For all future correspondences please mention the vendor code Collective RFQ Number & RFQ Number.
007	Retention Money 10 % shall stand deducted from each and every running bill submitted in the event of contract is awarded.

**LIST OF ENCLOSURES**

To: BPCL ESTIMATE MUMBAI - 400038 India (300648)

-----Tear off Portion to be pasted on the envelope containing offer-----

**Collective RFQ No. : 1000226746**

Our Reference:

Due Date : 18.02.2015

RFQ No. : 6000808384

Due Time : 11:00:00

Subject: CONSTRUCTION OF NRO AT DEVALIYA DIST NARMADA

To,

Purchase Group : E75-CONS GRP HAZIRA